Bid Sheet

Persigo Wash Siphon Lid Replacement

12/28/2008

| Lid replacement | | | | | Engineers Estimate | | BPS Concrete | | Sorter Construction | | MA Concrete | | Mays Concrete | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Item | Reference | Description | Quantity | Unit | Unit Price | Total Price | Unit Price | Total Price | Unit Price | Total Price | Unit Price | Total Price | Unit Price | Total Price |
| 1 | 202.12 | Saw cut existing lid off from existing vaults | 140 | LF | $ 20.00 | $ 2,800.00 | $ 38.50 | $ 5,390.00 | $ 40.00 | $ 5,600.00 | $ 43.00 | $ 6,020.00 | $ 65.71 | $ 9,199.40 |
| 2 | 202 | Remove vegitation around the existing vaults | 1 | LS | $ 200.00 | $ 200.00 | $ 800.00 | $ 800.00 | $ 500.00 | $ 500.00 | $ 400.00 | $ 400.00 | $ 375.00 | $ 375.00 |
| 3 | 202 | Remove and dispose of the existing lids | 2 | EA | $ 2,000.00 | $ 4,000.00 | $ 2,808.00 | $ 5,616.00 | $ 2,100.00 | $ 4,200.00 | $ 1,333.00 | $ 2,666.00 | $ 1,680.00 | $ 3,360.00 |
| 4 | 601 | New lid west vault precast and installed | 1 | EA | $ 20,000.00 | $ 20,000.00 | $ 16,540.20 | $ 16,540.20 | $ 17,100.00 | $ 17,100.00 | $ 18,195.00 | $ 18,195.00 | $ 22,250.00 | $ 22,250.00 |
| 5 | 601 | New lid east vault precast and installed | 1 | EA | $ 20,000.00 | $ 20,000.00 | $ 17,917.20 | $ 17,917.20 | $ 18,500.00 | $ 18,500.00 | $ 19,725.00 | $ 19,725.00 | $ 24,780.00 | $ 24,780.00 |
| 6 | 102.7 | Paint the underside of the new lids with Sherwin Williams COR-COATE SC | 500 | SF | $ 3.00 | $ 1,500.00 | $ 2.67 | $ 1,335.00 | $ 5.00 | $ 2,500.00 | $ 17.50 | $ 8,750.00 | $ 2.85 | $ 1,425.00 |
| 7 | 102.7 | Seal the new lid to the existing box with de neef Swellseal WA Polyurethane Water stop | 140 | LF | $ 5.00 | $ 700.00 | $ 5.89 | $ 824.60 | $ 9.00 | $ 1,260.00 | $ 14.14 | $ 1,979.60 | $ 5.04 | $ 705.60 |
| 8 | | Force Account | 1 | LS | | $ 1,500.00 | | $ 1,500.00 | | $ 1,500.00 | | $ 1,500.00 | | $ 1,500.00 |
| | | Total price | | | | $ 50,700.00 | | $ 49,923.00 | | $ 51,160.00 | | $ 59,235.60 | | $ 63,595.00 |

Bidder Signature

Date: