

Bid Summary

2009 SANITARY Sewer Replacement Project

Bid Opening: Enter Bid Opening date (m/d/y) < Enter the "Bid Opening date:" in the "Data" worksheet.

By: David Donohue, Project Engineer

Engineer's Estimate Sorter Construction Mendez, Inc. MA Concrete Construction KR Swedfeger Construction

Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Low Unit Price	High Unit Price	Median Unit Price	Average Unit Price
1	202	REMOVAL OF ASPHALT MAT. CUT AND REMOVE AS SHOWN.	5,000.	SY	\$ 3.00	\$ 15,000.00	\$ 3.00	\$ 15,000.00	\$ 1.70	\$ 8,500.00	\$ 2.36	\$ 11,800.00	\$ 2.00	\$ 10,000.00	\$ 1.70	\$ 3.00	\$ 4,250.00	\$ 2.27
3	202	REMOVAL OF CONCRETE. SAW CUT AND REMOVE CONCRETE AS SHOWN. INCLUDES BUT NOT LIMITED TO CURB, GUTTER, SIDEWALK, DRIVEWAY, SLABS, V-PAN, CURB RAMPS, INTERSECTION CORNERS, APRONS, AND LANDSCAPE BORDERS.	500.	SY	\$ 11.00	\$ 5,500.00	\$ 4.50	\$ 2,250.00	\$ 6.70	\$ 3,350.00	\$ 8.71	\$ 4,355.00	\$ 2.00	\$ 1,000.00	\$ 2.00	\$ 8.71	\$ 500.00	\$ 5.48
4	202	REMOVAL OF TREE (SIZE AS SHOWN ON PLAN)	1.	EA	\$ 700.00	\$ 700.00	\$ 370.00	\$ 370.00	\$ 190.00	\$ 190.00	\$ 390.00	\$ 390.00	\$ 1,500.00	\$ 1,500.00	\$ 190.00	\$ 1,500.00	\$ 95.00	\$ 612.50
5	202	REMOVAL OF BUSH	4.	EA	\$ 300.00	\$ 1,200.00	\$ 115.00	\$ 460.00	\$ 26.00	\$ 104.00	\$ 49.25	\$ 197.00	\$ 740.00	\$ 2,960.00	\$ 26.00	\$ 740.00	\$ 52.00	\$ 232.56
16	202	REMOVAL OF MANHOLE. CONTRACTOR SHALL SALVAGE RING AND COVER AND DELIVER TO CITY SHOPS.	19.	EA	\$ 700.00	\$ 13,300.00	\$ 400.00	\$ 7,600.00	\$ 482.00	\$ 9,158.00	\$ 296.74	\$ 5,638.06	\$ 370.00	\$ 7,030.00	\$ 296.74	\$ 482.00	\$ 2,819.03	\$ 387.19
24	210	RESET LANDSCAPE APPURTENANCE.	5.	EA	\$ 100.00	\$ 500.00	\$ 215.00	\$ 1,075.00	\$ 103.00	\$ 515.00	\$ 218.00	\$ 1,090.00	\$ 1,200.00	\$ 6,000.00	\$ 103.00	\$ 1,200.00	\$ 257.50	\$ 434.00
101	210	RESET SPRINKLER SYSTEM, AS NEEDED (COMPLETE IN PLACE)	1.	LS	\$ 5,000.00	\$ 5,000.00	\$ 1,350.00	\$ 1,350.00	\$ 2,135.00	\$ 2,135.00	\$ 3,180.00	\$ 3,180.00	\$ 3,700.00	\$ 3,700.00	\$ 1,350.00	\$ 3,700.00	\$ 675.00	\$ 2,591.25
102	210	RESET FENCE AND GATE AS REQUIRED. (HEIGHT AND MATERIAL AS SHOW ON PLAN)	138.	LF	\$ 23.00	\$ 3,174.00	\$ 15.00	\$ 2,070.00	\$ 25.50	\$ 3,519.00	\$ 28.16	\$ 3,886.08	\$ 36.00	\$ 4,968.00	\$ 15.00	\$ 36.00	\$ 1,035.00	\$ 26.17
129	210	RESET IRRIGATION PUMP. INCLUDES RESET AND RECONNECTION OF PIPE, FITTINGS, PUMP, ELECTRICAL, SHELTER, AND ANY/ALL MOUNTING PANELS.	4.	EA	\$ 750.00	\$ 3,000.00	\$ 160.00	\$ 640.00	\$ 162.00	\$ 648.00	\$ 268.00	\$ 1,072.00	\$ 1,200.00	\$ 4,800.00	\$ 160.00	\$ 1,200.00	\$ 320.00	\$ 447.50
200	102.11/108.5	STORM SEWER BASIC MANHOLE (48" I.D.) INCLUDES CONNECTION OF ADJACENT STORM SEWER LINES, AND ADJUSTING TO FINAL GRADE. (SEE CITY OF GRAND JUNCTION STANDARD DETAIL D-03).	1.	EA	\$ 2,700.00	\$ 2,700.00	\$ 2,565.00	\$ 2,565.00	\$ 1,629.00	\$ 1,629.00	\$ 2,919.00	\$ 2,919.00	\$ 4,000.00	\$ 4,000.00	\$ 1,629.00	\$ 4,000.00	\$ 814.50	\$ 2,778.25
200B	102.11/108.5	STORM SEWER BASIC MANHOLE (36" I.D.). INCLUDES CONNECTION OF ADJACENT STORM SEWER LINES VIA CORING AND GROUTING AND ADJUSTING TO FINAL GRADE.	1.	EA	\$ 3,000.00	\$ 3,000.00	\$ 2,150.00	\$ 2,150.00	\$ 2,225.00	\$ 2,225.00	\$ 2,644.00	\$ 2,644.00	\$ 3,600.00	\$ 3,600.00	\$ 2,150.00	\$ 3,600.00	\$ 1,075.00	\$ 2,654.75
200C	102.11/108.5	STORM SEWER BASIC MANHOLE (24" I.D.). INCLUDES CONNECTION OF ADJACENT STORM SEWER LINE VIA CORING AND GROUTING, CONNECTING TO UNDERLYING STORM SEWER MAIN AS PER CONSTRUCTION DRAWING DETAIL, AND ADJUSTING TO FINAL GRADE.	1.	EA	\$ 4,000.00	\$ 4,000.00	\$ 1,500.00	\$ 1,500.00	\$ 2,097.00	\$ 2,097.00	\$ 2,119.00	\$ 2,119.00	\$ 3,400.00	\$ 3,400.00	\$ 1,500.00	\$ 3,400.00	\$ 750.00	\$ 2,279.00
204	102.13/108.6	SINGLE STORM DRAIN INLET (VERTICAL CURB) (SEE CITY OF GRAND JUNCTION STANDARD DETAIL D-07). INCLUDES CONNECTING LATERAL VIA CORING AND GROUTING THROUGH CORNER OF CATCH BASIN BOX.	1.	EA	\$ 1,700.00	\$ 1,700.00	\$ 2,450.00	\$ 2,450.00	\$ 2,547.00	\$ 2,547.00	\$ 2,935.00	\$ 2,935.00	\$ 3,100.00	\$ 3,100.00	\$ 2,450.00	\$ 3,100.00	\$ 1,225.00	\$ 2,758.00

Bid Summary																					
2009 SANITARY Sewer Replacement Project																					
Bid Opening:		Enter Bid Opening date (m/d/y)		< Enter the "Bid Opening date:" in the "Data" worksheet.																	
By:		David Donohue, Project Engineer																			
		Engineer's Estimate				Sorter Construction				Mendez, Inc.				MA Concrete Construction				KR Swedfeger Construction			
Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Low Unit Price	High Unit Price	Median Unit Price	Average Unit Price			
215	102.10/108.2	6" STORM DRAIN PIPE (C-900 PVC). INCLUDES TYPE A BEDDING AND HAUNCHING MATERIAL AND BACKFILL OF TRENCH WITH NATIVE MATERIALS MEETING 103.16 EARTH BACKFILL MATERIAL.	140.	LF	\$ 45.00	\$ 6,300.00	\$ 29.00	\$ 4,060.00	\$ 35.00	\$ 4,900.00	\$ 60.38	\$ 8,453.20	\$ 60.00	\$ 8,400.00	\$ 29.00	\$ 60.38	\$ 2,030.00	\$ 46.10			
218	102.10/108.2	12-INCH STORM DRAIN PIPE (PVC, SDR-35)(INCLUDES CALDER/FERNCO COUPLINGS AT TIE-IN ENDS). INCLUDES TYPE A BEDDING AND HAUNCHING MATERIAL AND BACKFILL OF TRENCH WITH NATIVE MATERIALS IF ACCEPTABLE OR IMPORTED BACKFILL MEETING 103.16.	40.	LF	\$ 50.00	\$ 2,000.00	\$ 35.00	\$ 1,400.00	\$ 36.00	\$ 1,440.00	\$ 81.15	\$ 3,246.00	\$ 63.00	\$ 2,520.00	\$ 35.00	\$ 81.15	\$ 700.00	\$ 53.79			
253	102.14	CONNECT NEW 6" C-900 PVC STORM TO EXISTING 60" STORM	1.	EA	\$ 500.00	\$ 500.00	\$ 1,350.00	\$ 1,350.00	\$ 687.00	\$ 687.00	\$ 487.00	\$ 487.00	\$ 650.00	\$ 650.00	\$ 487.00	\$ 1,350.00	\$ 243.50	\$ 793.50			
254	102.14	GROUT-SEAL HOLE OPENING IN MAHOLE, CATCH BASIN, OR PIPE STUB; DIA. 18 INCHES OR LESS.	9.	EA	\$ 300.00	\$ 2,700.00	\$ 160.00	\$ 1,440.00	\$ 108.00	\$ 972.00	\$ 488.00	\$ 4,392.00	\$ 370.00	\$ 3,330.00	\$ 108.00	\$ 488.00	\$ 486.00	\$ 281.50			
269A	UU/108.2	BYPASS PUMPING FOR ALL OPERATIONS ON SEWER IMPROVEMENTS IN COLORADO AVE./UTE AVE. ALLEY. BYPASS CONFIGURATION SHALL ALLOW CONTINUOUS TRAFFIC USAGE OF AFFECTED STREETS. CONTRACTOR SHALL INDEPENDENTLY VERIFY FLOW RATES.	1.	LS	\$ 15,000.00	\$ 15,000.00	\$ 3,000.00	\$ 3,000.00	\$ 8,327.00	\$ 8,327.00	\$ 7,700.00	\$ 7,700.00	\$ 10,000.00	\$ 10,000.00	\$ 3,000.00	\$ 10,000.00	\$ 1,500.00	\$ 7,256.75			
269B	UU/108.2	BYPASS PUMPING FOR ALL OPERATIONS IMPACTING 2897 ORCHARD AVENUE. INCLUDES SERVICE ENTERING MANHOLE E2-282-060 AND SERVICE LOCATED 23 FT SOUTH OF MANHOLE AND ANY AND ALL OTHER SERVICES NOT PREVIOUSLY LOCATED ASSOCIATED WITH THIS ADDRESS. SANITARY SERVICE SHALL REMAIN IN OPERATION AT ALL TIMES DURING CONSTRUCTION AFFECTING THIS ADDRESS.	1.	LS	\$ 2,500.00	\$ 2,500.00	\$ 2,700.00	\$ 2,700.00	\$ 2,163.00	\$ 2,163.00	\$ 2,000.00	\$ 2,000.00	\$ 2,800.00	\$ 2,800.00	\$ 2,000.00	\$ 2,800.00	\$ 1,000.00	\$ 2,415.75			
269C	UU/108.2	BYPASS PUMPING FOR ALL OPERATIONS IMPACTING MANHOLE REMOVAL AND REPLACEMENT AT 19TH STREET AND GUNNISON AVE. CONTRACTOR SHALL INDEPENDENTLY VERIFY FLOW RATES.	1.	LS	\$ 7,500.00	\$ 7,500.00	\$ 750.00	\$ 750.00	\$ 787.00	\$ 787.00	\$ 2,000.00	\$ 2,000.00	\$ 8,700.00	\$ 8,700.00	\$ 750.00	\$ 8,700.00	\$ 375.00	\$ 3,059.25			

Bid Summary																					
2009 SANITARY Sewer Replacement Project																					
Bid Opening:		Enter Bid Opening date (m/d/y) < Enter the "Bid Opening date:" in the "Data" worksheet.																			
By:		David Donohue, Project Engineer																			
		Engineer's Estimate				Sorter Construction				Mendez, Inc.				MA Concrete Construction				KR Swedfeger Construction			
Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Low Unit Price	High Unit Price	Median Unit Price	Average Unit Price			
270	UU/108.	REMOVE AND REPAIR IRRIGATION LATERAL/MAIN, SIZE VARIES (4 - 12 INCHES). INCLUDES CUTTING AND REMOVAL OF CONFLICTING PIPE SECTION, SECURING OF WATER FLOWS, INSTALLATION OF REPAIR SECTION INCLUDING COUPLING(S), AND BEDDING, HAUNCHING, AND BACKFILL OF PIPE AS PER STANDARD SPECIFICATIONS FOR UNDERGROUND UTILITIES. PIPE SHALL BE PIP-PVC SDR 26 MEETING 102.10c. IRRIGATION/SPRINKLER SYSTEM COMPONENTS PAID FOR PER PAY ITEM 101	8.	EA	\$ 300.00	\$ 2,400.00	\$ 360.00	\$ 2,880.00	\$ 168.00	\$ 1,344.00	\$ 443.00	\$ 3,544.00	\$ 2,500.00	\$ 20,000.00	\$ 168.00	\$ 2,500.00	\$ 672.00	\$ 867.75			
300	102.11/1 08.5	SANITARY SEWER BASIC MANHOLE (48" I.D.)(DEPTH ≤ 5') . INCLUDES CONNECTION OF ADJACENT SEWER LINES (INCLUDING PIPE STUB LENGTHS AND COUPLINGS), FORMING INVERTS AND ADJUSTING TO FINAL GRADE. (SEE CITY OF GRAND JUNCTION STANDARD DETAIL SS-02).	19.	EA	\$ 2,300.00	\$ 43,700.00	\$ 1,975.00	\$ 37,525.00	\$ 3,565.00	\$ 67,735.00	\$ 2,569.00	\$ 48,811.00	\$ 2,600.00	\$ 49,400.00	\$ 1,975.00	\$ 3,565.00	\$ 18,762.50	\$ 2,677.25			
300B	102.11/1 08.5	SANITARY SEWER BASIC MANHOLE (60" I.D.)(DEPTH AS SHOWN ON PLANS) . INCLUDES CONNECTION OF ADJACENT SEWER LINES (INCLUDING PIPE STUB LENGTHS AND COUPLINGS), FORMING INVERTS AND ADJUSTING TO FINAL GRADE. (SEE CITY OF GRAND JUNCTION STANDARD DETAIL SS-02).	1.	EA	\$ 4,500.00	\$ 4,500.00	\$ 3,800.00	\$ 3,800.00	\$ 4,315.00	\$ 4,315.00	\$ 3,894.00	\$ 3,894.00	\$ 4,200.00	\$ 4,200.00	\$ 3,800.00	\$ 4,315.00	\$ 1,900.00	\$ 4,052.25			
306	102.11/1 08.5	MANHOLE BARREL SECTION (DEPTH>5')(DIA. = 48"). INCLUDES STORM SEWER AND SANITARY SEWER MAHNOLE BARREL SECTIONS.	45.	VLF	\$ 110.00	\$ 4,950.00	\$ 145.00	\$ 6,525.00	\$ 129.00	\$ 5,805.00	\$ 69.00	\$ 3,105.00	\$ 145.00	\$ 6,525.00	\$ 69.00	\$ 145.00	\$ 1,552.50	\$ 122.00			
310	102.11/1 08.5	CONNECT TO EXISTING INLET (6" PIPE). (SEE CITY OF GRAND JUNCTION STANDARD DETAIL SS-08).	3.	EA	\$ 350.00	\$ 1,050.00	\$ 575.00	\$ 1,725.00	\$ 305.00	\$ 915.00	\$ 552.00	\$ 1,656.00	\$ 500.00	\$ 1,500.00	\$ 305.00	\$ 575.00	\$ 457.50	\$ 483.00			
311	102.11/1 08.5	CONNECT TO EXISTING MANHOLE (4", 6" OR 8" PIPE). (SEE CITY OF GRAND JUNCTION STANDARD DETAIL SS-08). CONTRACTOR SHALL CONNECT THE SEWER PIPE TO THE EXISTING MANHOLE IN SUCH A WAY THAT ENSURES A WATERTIGHT CONNECTION. CONTRACTOR SHALL RECONSTRUCT MH INVERT, COST SHALL BE INCIDENTAL TO THE COST OF "CONNECT TO EXISTING MANHOLE" BID ITEM	25.	EA	\$ 600.00	\$ 15,000.00	\$ 870.00	\$ 21,750.00	\$ 587.00	\$ 14,675.00	\$ 440.00	\$ 11,000.00	\$ 500.00	\$ 12,500.00	\$ 440.00	\$ 870.00	\$ 5,500.00	\$ 599.25			

Bid Summary																		
2009 SANITARY Sewer Replacement Project																		
Bid Opening:		Enter Bid Opening date (m/d/y) < Enter the "Bid Opening date:" in the "Data" worksheet.																
By:		David Donohue, Project Engineer																
		Engineer's Estimate				Sorter Construction				Mendez, Inc.				MA Concrete Construction		KR Swedfeger Construction		
Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Low Unit Price	High Unit Price	Median Unit Price	Average Unit Price
321	102.9/108.2	4" GRAVITY SEWER PIPE (SDR 35 PVC). INCLUDES CONNECTION TO EXISTING/NEW LINE/TAP. INCLUDES TYPE A BEDDING AND HAUNCHING MATERIAL AND BACKFILL OF TRENCH WITH NATIVE MATERIALS OR IMPORTED MATERIALS MEETING 103.16 EARTH BACKFILL MATERIAL, AS DETERMINED OR AGREED TO BY THE ENGINEER.	1,384.	LF	\$ 25.00	\$ 34,600.00	\$ 50.00	\$ 69,200.00	\$ 51.00	\$ 70,584.00	\$ 53.66	\$ 74,265.44	\$ 63.00	\$ 87,192.00	\$ 50.00	\$ 63.00	\$ 34,600.00	\$ 54.42
329	102.9/108.2	8" GRAVITY SEWER PIPE (ASTM D-3034 SDR-35 PVC). INCLUDES TYPE A BEDDING AND HAUNCHING MATERIAL AND BACKFILL OF TRENCH WITH NATIVE MATERIALS OR IMPORTED MATERIALS MEETING 103.16 EARTH BACKFILL MATERIAL, AS DETERMINED OR AGREED TO BY THE ENGINEER.	4,850.	LF	\$ 37.00	\$ 179,450.00	\$ 41.00	\$ 198,850.00	\$ 32.00	\$ 155,200.00	\$ 60.00	\$ 291,000.00	\$ 65.00	\$ 315,250.00	\$ 32.00	\$ 65.00	\$ 77,600.00	\$ 49.50
329A	102.9/108.2	6" GRAVITY SEWER PIPE (ASTM D-3034 SDR-35 PVC). INCLUDES TYPE A BEDDING AND HAUNCHING MATERIAL AND BACKFILL OF TRENCH WITH NATIVE MATERIALS OR IMPORTED MATERIALS MEETING 103.16 EARTH BACKFILL MATERIAL, AS DETERMINED OR AGREED TO BY THE ENGINEER.	2,200.	LF	\$ 35.00	\$ 77,000.00	\$ 38.00	\$ 83,600.00	\$ 34.00	\$ 74,800.00	\$ 63.00	\$ 138,600.00	\$ 63.00	\$ 138,600.00	\$ 34.00	\$ 63.00	\$ 37,400.00	\$ 49.50
329B	102.108.2	8-INCH CURED IN PLACE PIPE (CIPP); DESIGNED, SUBMITTED, AND STAMPED BY P.E.; INSTALLED BY CONTRACTOR OR SUBCONTRACTOR MEETING SPECIFICATIONS DEFINED IN CONTRACT DOCUMENTS. SEE SPECIAL PROVISIONS. DESIGN SHALL BE FOR EXISTING PIPE IN FULLY DETERIORATED CONDITION. CONTRACTOR SHALL VERIFY DIA. OF PIPE PRIOR TO DESIGN AND FABRICATION OF LINER.	2,576.	LF	\$ 90.00	\$ 231,840.00	\$ 30.00	\$ 77,280.00	\$ 45.50	\$ 117,208.00	\$ 43.00	\$ 110,768.00	\$ 53.00	\$ 136,528.00	\$ 30.00	\$ 53.00	\$ 38,640.00	\$ 42.88
347	102.9/108.2	8" x 4" SEWER SERVICE TAP (NEW SERVICE ON NEWLY INSTALLED PVC PIPE), TO INCLUDE: FULL BODY WYE, W/ STREET 45, ALL BENDS AND FITTINGS, CLEANOUT, VERTICAL PIPING, TRACING WIRE, CLEANOUT RING & COVER AND CONCRETE COLLAR, AS REQUIRED, TO ALIGN AND CONNECT TO EXISTING SERVICE AT ROW LINE. 4" SERVICE PIPE SEPARATE. (SEE CITY OF GRAND JUNCTION STANDARD DETAIL "TYPICAL SERVICE "Y" CONNECTION" SS-06 AND SS-07)	105.	EA	\$ 900.00	\$ 94,500.00	\$ 240.00	\$ 25,200.00	\$ 266.00	\$ 27,930.00	\$ 192.00	\$ 20,160.00	\$ 420.00	\$ 44,100.00	\$ 192.00	\$ 420.00	\$ 10,080.00	\$ 279.50

Bid Summary																		
2009 SANITARY Sewer Replacement Project																		
Bid Opening:		Enter Bid Opening date (m/d/y) < Enter the "Bid Opening date:" in the "Data" worksheet.																
By:		David Donohue, Project Engineer																
		Engineer's Estimate				Sorter Construction				Mendez, Inc.				MA Concrete Construction		KR Swedfeger Construction		
Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Low Unit Price	High Unit Price	Median Unit Price	Average Unit Price
347A	102.9/10 4.2/108. 2	6" x 4" SEWER SERVICE TAP (NEW SERVICE ON NEWLY INSTALLED PVC PIPE), TO INCLUDE: FULL BODY WYE, W/ STREET 45, ALL BENDS AND FITTINGS, CLEANOUT, VERTICAL PIPING, TRACING WIRE, CLEANOUT RING & COVER AND CONCRETE COLLAR, AS REQUIRED, TO ALIGN AND CONNECT TO EXISTING SERVICE AT ROW LINE. 4" SERVICE PIPE SEPARATE. (SEE CITY OF GRAND JUNCTION STANDARD DETAIL "TYPICAL SERVICE "Y" CONNECTION" SS-06 AND SS-07)	70.	EA	\$ 850.00	\$ 59,500.00	\$ 230.00	\$ 16,100.00	\$ 255.00	\$ 17,850.00	\$ 182.00	\$ 12,740.00	\$ 410.00	\$ 28,700.00	\$ 182.00	\$ 410.00	\$ 6,370.00	\$ 269.25
347B	102.9/10 4.2/108. 2	6" x 4" SEWER SERVICE TAP (NEW SERVICE ON EXISTING PIPE UNDERGOING TRENCHLESS REPAIR), TO INCLUDE: DISCONNECTING EXISTING SERVICE AND INSTALLING NEW SERVICE TAP. NEW TAP SHALL BE (W/ APPROVAL OF ENGINEER OR INSPECTOR ON CASE-SPECIFIC BASIS): FULL BODY WYE W/ STREET 45 (PIPE STUBS AND COUPLINGS INCLUDED), INSERTA-TEE, OR SADDLE; ALL BENDS AND FITTINGS, CLEANOUT, VERTICAL PIPING, TRACING WIRE, CLEANOUT RING & COVER AND CONCRETE COLLAR, AS REQUIRED, TO ALIGN AND CONNECT TO EXISTING SERVICE AT ROW LINE. 4" SERVICE PIPE SEPARATE. (SEE CITY OF GRAND JUNCTION STANDARD DETAIL "TYPICAL SERVICE "Y" CONNECTION" SS-06 AND SS-07)	1.	EA	\$ 950.00	\$ 950.00	\$ 410.00	\$ 410.00	\$ 646.00	\$ 646.00	\$ 2,600.00	\$ 2,600.00	\$ 1,500.00	\$ 1,500.00	\$ 410.00	\$ 2,600.00	\$ 205.00	\$ 1,289.00
347C	102.9/10 4.2/108. 2	8" x 4" SEWER SERVICE TAP. NEW SERVICE ON EXISTING SHALLOW PIPE (DEPTH 6' OR LESS) UNDERGOING TRENCHLESS REPAIR, TO INCLUDE: DISCONNECTING EXISTING SERVICE AND INSTALLING NEW SERVICE TAP AFTER TRENCHLESS REHAB (NEW TAP SHALL BE INSERTA-TEE); ALL BENDS AND FITTINGS, CLEANOUT, VERTICAL PIPING, TRACING WIRE, CLEANOUT RING & COVER AND CONCRETE COLLAR, AS REQUIRED, TO ALIGN AND CONNECT TO EXISTING SERVICE AT ROW LINE. 4" SERVICE PIPE SEPARATE. (SEE CITY OF GRAND JUNCTION STANDARD DETAIL "TYPICAL SERVICE "Y" CONNECTION" SS-06 AND SS-07)	11.	EA	\$ 450.00	\$ 4,950.00	\$ 405.00	\$ 4,455.00	\$ 342.00	\$ 3,762.00	\$ 1,900.00	\$ 20,900.00	\$ 1,500.00	\$ 16,500.00	\$ 342.00	\$ 1,900.00	\$ 1,881.00	\$ 1,036.75
347D	102.9/10 4.2/108. 2	CIPP TRENCHLESS SANITARY SEWER SERVICE CONNECTION (TOPHAT); 4" DIA SERVICE; MAIN DIA. VARIES.	22.	EA	\$ 1,900.00	\$ 41,800.00	\$ 4,180.00	\$ 91,960.00	\$ 2,203.00	\$ 48,466.00	\$ 1,900.00	\$ 41,800.00	\$ 2,400.00	\$ 52,800.00	\$ 1,900.00	\$ 4,180.00	\$ 20,900.00	\$ 2,670.75

Bid Summary

2009 SANITARY Sewer Replacement Project

Bid Opening: Enter Bid Opening date (m/d/y) < Enter the "Bid Opening date:" in the "Data" worksheet.

By: David Donohue, Project Engineer

Item No.	CDOT, City Ref.	Description	Quantity	Units	Engineer's Estimate		Sorter Construction		Mendez, Inc.		MA Concrete Construction		KR Swedfeger Construction		Low Unit Price	High Unit Price	Median Unit Price	Average Unit Price
					Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price				
347E	102.9/104.2/108.2	8" x 4" SEWER SERVICE TAP. NEW SERVICE ON EXISTING DEEP PIPE (DEPTH GREATER THAN 6 FEET) UNDERGOING TRENCHLESS REPAIR, TO INCLUDE: DISCONNECTING EXISTING SERVICE AND INSTALLING NEW SERVICE TAP PRIOR TO CIPP INSTALLATION. NEW TAP SHALL BE (W/ APPROVAL OF ENGINEER OR INSPECTOR ON CASE-SPECIFIC BASIS): FULL BODY WYE W/ STREET 45 (PIPE STUBS AND COUPLINGS INCLUDED), INSERT-A-TEE, OR SADDLE; ALL BENDS AND FITTINGS, CLEANOUT, VERTICAL PIPING, TRACING WIRE, CLEANOUT RING & COVER AND CONCRETE COLLAR, AS REQUIRED, TO ALIGN AND CONNECT TO EXISTING SERVICE AT ROW LINE. 4" SERVICE PIPE SEPARATE. (SEE CITY OF GRAND JUNCTION STANDARD DETAIL "TYPICAL SERVICE "Y" CONNECTIONS SS-06 AND SS-07).	12.	EA	\$ 1,900.00	\$ 22,800.00	\$ 830.00	\$ 9,960.00	\$ 2,495.00	\$ 29,940.00	\$ 2,200.00	\$ 26,400.00	\$ 2,500.00	\$ 30,000.00	\$ 830.00	\$ 2,500.00	\$ 4,980.00	\$ 2,006.25
356	104.4	ENCASE SEWER PIPE IN REINFORCED CONCRETE PER STD. DETAIL GU-04.	20.	LF	\$ 40.00	\$ 800.00	\$ 25.00	\$ 500.00	\$ 36.00	\$ 720.00	\$ 38.20	\$ 764.00	\$ 150.00	\$ 3,000.00	\$ 25.00	\$ 150.00	\$ 250.00	\$ 62.30
360	206	STRUCTURE BACKFILL (FLOWFILL). USE FOR BACKFILL BENEATH WATER, STORM, IRR LINES; EXTEND 5 FT EITHER SIDE OF UPPER UTILITY.	150.	CY	\$ 70.00	\$ 10,500.00	\$ 100.00	\$ 15,000.00	\$ 84.00	\$ 12,600.00	\$ 76.16	\$ 11,424.00	\$ 120.00	\$ 18,000.00	\$ 76.16	\$ 120.00	\$ 5,712.00	\$ 95.04
361	103.16108.2	IMPORTED TRENCH BACKFILL (PIT RUN). INCLUDES DISPOSAL OF UNSUITABLE AND/OR EXCESS MATERIAL AT DISPOSAL SITE PROCURED BY CONTRACTOR.	7,000.	TON	\$ 10.00	\$ 70,000.00	\$ 12.00	\$ 84,000.00	\$ 12.80	\$ 89,600.00	\$ 14.00	\$ 98,000.00	\$ 20.00	\$ 140,000.00	\$ 12.00	\$ 20.00	\$ 42,000.00	\$ 14.70
362	103.15/108.7	OVEREXCAVATION AND GRANULAR STABILIZATION MATERIAL (TYPE B).	2,000.	TON	\$ 17.00	\$ 34,000.00	\$ 20.00	\$ 40,000.00	\$ 17.75	\$ 35,500.00	\$ 17.00	\$ 34,000.00	\$ 21.00	\$ 42,000.00	\$ 17.00	\$ 21.00	\$ 17,000.00	\$ 18.94
364	104.2	INSTALL SANITARY SEWER CLEANOUT, CLEANOUT RING & COVER AND CONCRETE COLLAR (SS-07). INCLUDES CONNECTING TO EXISTING PIPE.	1.	EA	\$ 850.00	\$ 850.00	\$ 175.00	\$ 175.00	\$ 161.00	\$ 161.00	\$ 654.00	\$ 654.00	\$ 500.00	\$ 500.00	\$ 161.00	\$ 654.00	\$ 80.50	\$ 372.50
364A	104.2	INSTALL STORM SEWER CLEANOUT, CLEANOUT RING & COVER AND CONCRETE COLLAR (SS-07).	1.	EA	\$ 950.00	\$ 950.00	\$ 580.00	\$ 580.00	\$ 531.00	\$ 531.00	\$ 754.00	\$ 754.00	\$ 800.00	\$ 800.00	\$ 531.00	\$ 800.00	\$ 265.50	\$ 666.25
366	103	EXCAVATE LAUNCHING/RECEIVING PIT FOR HDD, IMPACTOR DEVICE, HDPE ADAPTER AND HDPE PIPE. BACK FILL TRENCH WITH NATIVE MATERIALS OR IMPORTED MATERIALS MEETING 103.16 EARTH BACK FILL MATERIAL, AS DETERMINED OR AGREED TO BY ENGINEER. COST OF BACKFILL IS INCIDENTAL TO THIS PAY ITEM.	3.	EA	\$ 4,000.00	\$ 12,000.00	\$ 865.00	\$ 2,595.00	\$ 1,298.00	\$ 3,894.00	\$ 1,600.00	\$ 4,800.00	\$ 3,000.00	\$ 9,000.00	\$ 865.00	\$ 3,000.00	\$ 1,297.50	\$ 1,690.75

Bid Summary																		
2009 SANITARY Sewer Replacement Project																		
Bid Opening:		Enter Bid Opening date (m/d/y) < Enter the "Bid Opening date:" in the "Data" worksheet.																
By:		David Donohue, Project Engineer																
		Engineer's Estimate				Sorter Construction				Mendez, Inc.				MA Concrete Construction		KR Swedfeger Construction		
Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Low Unit Price	High Unit Price	Median Unit Price	Average Unit Price
367	102.9/10 8.2	INSTALL NEW 6" HIGH DENSITY POLYETHYLENE (HDPE) SDR-17 SEWER PIPE FOR PIPE BURSTING. ANY/ALL ADAPTER PIPE SEGMENTS AND FITTINGS AT ENDS REQUIRED FOR CONNECTION TO MANHOLES SHALL BE INCIDENTAL TO THIS TRENCHLESS INSTALLATION OF NEW 8" SANITARY SEWER IN FULLY DETERIORATED 8" VCP. P.E.-DESIGNED 8" CIPP OR HIGH DENSITY POLYETHYLENE (HDPE) SDR-17 (ASTM F714, D3550, AND D3035) INSTALLED VIA PIPE BURSTING. LAUNCHING/RECEIVING PITS INCIDENTAL.	658.	LF	\$ 110.00	\$ 72,380.00	\$ 57.00	\$ 37,506.00	\$ 56.25	\$ 37,012.50	\$ 56.00	\$ 36,848.00	\$ 67.00	\$ 44,086.00	\$ 56.00	\$ 67.00	\$ 18,424.00	\$ 59.06
367B	102.9/10 8.2	TRENCHLESS INSTALLATION OF NEW 8" SANITARY SEWER IN FULLY DETERIORATED 8" VCP. P.E.-DESIGNED 8" CIPP OR HIGH DENSITY POLYETHYLENE (HDPE) SDR-17 (ASTM F714, D3550, AND D3035) INSTALLED VIA PIPE BURSTING. LAUNCHING/RECEIVING PITS INCIDENTAL.	642.	LF	\$ 130.00	\$ 83,460.00	\$ 30.00	\$ 19,260.00	\$ 45.50	\$ 29,211.00	\$ 44.00	\$ 28,248.00	\$ 56.00	\$ 35,952.00	\$ 30.00	\$ 56.00	\$ 9,630.00	\$ 43.88
368	102.11/1 02.14/10 8.2	RECONDITION EXISTING MANHOLE BENCH. REMOVE DETERIORATED CONCRETE ON BENCH AND AROUND BASE USING ACID ETCH OR CHIPHAMMERING; CLEAN AND REMOVE DEBRIS; SATURATE SURFACE WITH ACRYLIC FORTIFIER; ADD XYPEX C-500 TO GROUT (GROUT MIX AS PER UU SPECS.) AT 3% PER WEIGHT OF CEMENTITIOUS MATERIAL. APPLY EPOXY COATING (MEETING UU SPECS) OR XYPEX PRODUCT CONCENTRATE SLURRY 1/16" THICK (CURE AS PER MFG. SPECS) AFTER GROUT HAS CURED. ANY BYPASS PUMPING SHALL BE INCIDENTAL	14.	EA	\$ 1,250.00	\$ 17,500.00	\$ 1,600.00	\$ 22,400.00	\$ 541.00	\$ 7,574.00	\$ 493.00	\$ 6,902.00	\$ 750.00	\$ 10,500.00	\$ 493.00	\$ 1,600.00	\$ 3,451.00	\$ 846.00
369	104/108. 5	ABANDON 4' DIA. MANHOLE; REMOVE CONE; RING AND COVER TO CITY SHOPS; FILL BASE W/ 1 FT CLASS B CONCRETE, THEN COMPACTED PIT RUN TO SUBGRADE. ALL WORK EXCEPT ROAD BASE AND ASPHALT PATCH PAID FOR UNDER THIS PAY ITEM.	3.	EA	\$ 650.00	\$ 1,950.00	\$ 555.00	\$ 1,665.00	\$ 595.00	\$ 1,785.00	\$ 428.00	\$ 1,284.00	\$ 680.00	\$ 2,040.00	\$ 428.00	\$ 680.00	\$ 642.00	\$ 564.50
371		Deleted			\$ 700.00						\$ -		\$ -					
555	608.06	CONCRETE SIDEWALK (4" THICK)	20.	SY	\$ 75.00	\$ 1,500.00	\$ 62.00	\$ 1,240.00	\$ 61.50	\$ 1,230.00	\$ 50.40	\$ 1,008.00	\$ 50.00	\$ 1,000.00	\$ 50.00	\$ 62.00	\$ 500.00	\$ 55.98
555A	608.06	CONCRETE SIDEWALK (8" THICK)	15.	SY	\$ 90.00	\$ 1,350.00	\$ 69.00	\$ 1,035.00	\$ 69.00	\$ 1,035.00	\$ 81.53	\$ 1,222.95	\$ 80.00	\$ 1,200.00	\$ 69.00	\$ 81.53	\$ 517.50	\$ 74.88
563	608.06	MONOLITHIC DRIVE OVER CURB, GUTTER AND SIDEWALK (MATCH EXISTING)(8" THICK)	20.	SY	\$ 95.00	\$ 1,900.00	\$ 41.00	\$ 820.00	\$ 42.00	\$ 840.00	\$ 60.00	\$ 1,200.00	\$ 54.00	\$ 1,080.00	\$ 41.00	\$ 60.00	\$ 410.00	\$ 49.25
569	608.06	MONOLITHIC VERTICAL CURB, GUTTER AND SIDEWALK (MATCH EXISTING)	25.	SY	\$ 95.00	\$ 2,375.00	\$ 114.00	\$ 2,850.00	\$ 114.00	\$ 2,850.00	\$ 56.40	\$ 1,410.00	\$ 54.00	\$ 1,350.00	\$ 54.00	\$ 114.00	\$ 675.00	\$ 84.60
576	608.06	CONCRETE DRIVEWAY SECTION (8" THICK) (COMMERCIAL)	30.	SY	\$ 95.00	\$ 2,850.00	\$ 79.00	\$ 2,370.00	\$ 79.60	\$ 2,388.00	\$ 70.73	\$ 2,121.90	\$ 68.00	\$ 2,040.00	\$ 68.00	\$ 79.60	\$ 1,020.00	\$ 74.33
577	608.06	CONCRETE DRIVEWAY SECTION (6" THICK) (RESIDENTIAL)	35.	SY	\$ 90.00	\$ 3,150.00	\$ 72.00	\$ 2,520.00	\$ 76.30	\$ 2,670.50	\$ 64.69	\$ 2,264.15	\$ 62.00	\$ 2,170.00	\$ 62.00	\$ 76.30	\$ 1,085.00	\$ 68.75
581	608.06	CONCRETE DRAINAGE PAN (6' WIDE)	16.	LF	\$ 60.00	\$ 960.00	\$ 39.00	\$ 624.00	\$ 42.50	\$ 680.00	\$ 56.00	\$ 896.00	\$ 54.00	\$ 864.00	\$ 39.00	\$ 56.00	\$ 312.00	\$ 47.88

Bid Summary																			
2009 SANITARY Sewer Replacement Project																			
Bid Opening:		Enter Bid Opening date (m/d/y) < Enter the "Bid Opening date:" in the "Data" worksheet.																	
By:		David Donohue, Project Engineer																	
		Engineer's Estimate					Sorter Construction				Mendez, Inc.		MA Concrete Construction		KR Swedfeger Construction				
Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Low Unit Price	High Unit Price	Median Unit Price	Average Unit Price	
584	608.06	CONCRETE DRAINAGE PAN (2.5' WIDE)	8.	LF	\$ 40.00	\$ 320.00	\$ 20.00	\$ 160.00	\$ 23.00	\$ 184.00	\$ 44.00	\$ 352.00	\$ 26.00	\$ 208.00	\$ 20.00	\$ 44.00	\$ 80.00	\$ 28.25	
602	608.06	CONCRETE CURB AND GUTTER (2' WIDE)	60.	LF	\$ 35.00	\$ 2,100.00	\$ 19.00	\$ 1,140.00	\$ 23.00	\$ 1,380.00	\$ 21.13	\$ 1,267.80	\$ 23.00	\$ 1,380.00	\$ 19.00	\$ 23.00	\$ 570.00	\$ 21.53	
603	608.06	CONCRETE CURB AND GUTTER (1'-6" WIDE)	225.	LF	\$ 30.00	\$ 6,750.00	\$ 16.00	\$ 3,600.00	\$ 23.00	\$ 5,175.00	\$ 19.46	\$ 4,378.50	\$ 22.00	\$ 4,950.00	\$ 16.00	\$ 23.00	\$ 1,800.00	\$ 20.12	
604	608	CONCRETE CURB RAMP	8.	SY	\$ 90.00	\$ 720.00	\$ 79.00	\$ 632.00	\$ 83.20	\$ 665.60	\$ 68.50	\$ 548.00	\$ 54.00	\$ 432.00	\$ 54.00	\$ 83.20	\$ 216.00	\$ 71.18	
605	608	DETECTABLE WARNING (SURFACE APPLIED OR WET SET)	8.	SF	\$ 40.00	\$ 320.00	\$ 55.00	\$ 440.00	\$ 54.00	\$ 432.00	\$ 47.00	\$ 376.00	\$ 60.00	\$ 480.00	\$ 47.00	\$ 60.00	\$ 188.00	\$ 54.00	
606	608	CONCRETE CURB (6" WIDE, 18" TOTAL HT.)	40.	LF	\$ 25.00	\$ 1,000.00	\$ 22.00	\$ 880.00	\$ 27.30	\$ 1,092.00	\$ 19.00	\$ 760.00	\$ 27.00	\$ 1,080.00	\$ 19.00	\$ 27.30	\$ 380.00	\$ 23.83	
636	608.06	CONCRETE PAVEMENT PATCH, 8" THICK, 6" CLASS 6 A.B.C., INCLUDES DOWELS AS PER STD. DETAIL IN STD. CONTRACT DOCUMENTS.	250.	SY	\$ 115.00	\$ 28,750.00	\$ 70.00	\$ 17,500.00	\$ 79.00	\$ 19,750.00	\$ 55.21	\$ 13,802.50	\$ 60.00	\$ 15,000.00	\$ 55.21	\$ 79.00	\$ 6,901.25	\$ 66.05	
663	304	AGGREGATE BASE COURSE (CLASS 6) (6" THICK)	4,700.	SY	\$ 7.50	\$ 35,250.00	\$ 8.00	\$ 37,600.00	\$ 7.40	\$ 34,780.00	\$ 5.64	\$ 26,508.00	\$ 7.00	\$ 32,900.00	\$ 5.64	\$ 8.00	\$ 13,254.00	\$ 7.01	
671	304	WASHED ROCK SURFACE COURSE FOR GRAVEL DRIVEWAYS. MATCH EXISTING TYPE. THICKNESS IS 2" MIN. AND 3" MAX.	160.	SY	\$ 6.50	\$ 1,040.00	\$ 4.50	\$ 720.00	\$ 6.80	\$ 1,088.00	\$ 6.68	\$ 1,068.80	\$ 4.00	\$ 640.00	\$ 4.00	\$ 6.80	\$ 320.00	\$ 5.50	
672	304	AGGREGATE BASE COURSE (CLASS 6) (4" THICK)	1,900.	SY	\$ 6.50	\$ 12,350.00	\$ 5.50	\$ 10,450.00	\$ 4.65	\$ 8,835.00	\$ 4.86	\$ 9,234.00	\$ 5.00	\$ 9,500.00	\$ 4.65	\$ 5.50	\$ 4,417.50	\$ 5.00	
681	401.08	HOT BITUMINOUS PAVEMENT (PATCHING) (3" THICK) (GRADING SX, BINDER GRADE PG 64-22); TWO 1.5-INCH LIFTS; INSTALLATION AND LIFT THICKNESSES SHALL CONFORM TO STANDARD CONTRACT DOCUMENT SPECIFICATIONS.	5,000.	SY	\$ 23.00	\$ 115,000.00	\$ 17.50	\$ 87,500.00	\$ 19.15	\$ 95,750.00	\$ 16.50	\$ 82,500.00	\$ 20.00	\$ 100,000.00	\$ 16.50	\$ 20.00	\$ 41,250.00	\$ 18.29	
681B	401.08	HOT BITUMINOUS PAVEMENT (PATCHING) (5" THICK) (GRADING SX, BINDER GRADE PG 64-22); ONE 3-INCH LIFT, ONE 2-INCH LIFT	550.	SY	\$ 50.00	\$ 27,500.00	\$ 27.00	\$ 14,850.00	\$ 29.50	\$ 16,225.00	\$ 25.50	\$ 14,025.00	\$ 32.00	\$ 17,600.00	\$ 25.50	\$ 32.00	\$ 7,012.50	\$ 28.50	
681C	401.08	T-TOP PAVEMENT PATCHING: MILL/PLANE 2" DEEPX2' WIDE PERIMETER AROUND ASPHALT PATCH AREA, PLACE 2" LIFT HOT BITUMINOUS PAVEMENT (GRADING AND GRADE TO MATCH PATCH SPEC.) LIFT, INTEGRAL W/ FINAL 2" LIFT OF PATCHING HBP.	200.	SY	\$ 65.00	\$ 13,000.00	\$ 23.00	\$ 4,600.00	\$ 17.70	\$ 3,540.00	\$ 25.00	\$ 5,000.00	\$ 20.00	\$ 4,000.00	\$ 17.70	\$ 25.00	\$ 1,770.00	\$ 21.43	
730	212	RESOD AREA AS SHOWN. INCLUDES STOCKPILE AND REUSE OF 12" OF EXISTING TOPSOIL(MUST BE KEPT FREE OF DETRITUS AND APPROVED BY INSPECTOR OR ENGINEER), OR IMPORT OF 12" OF NEW TOPSOIL, APPROVED BY INSPECTOR OR ENGINEER.	2,400.	SY	\$ 8.00	\$ 19,200.00	\$ 2.25	\$ 5,400.00	\$ 6.10	\$ 14,640.00	\$ 8.00	\$ 19,200.00	\$ 7.50	\$ 18,000.00	\$ 2.25	\$ 8.00	\$ 2,700.00	\$ 5.96	

Bid Summary																			
2009 SANITARY Sewer Replacement Project																			
Bid Opening:		Enter Bid Opening date (m/d/y)			< Enter the "Bid Opening date:" in the "Data" worksheet.														
By:		David Donohue, Project Engineer																	
		Engineer's Estimate					Sorter Construction				Mendez, Inc.			MA Concrete Construction		KR Swedfeger Construction			
Item No.	CDOT, City Ref.	Description	Quantity	Units	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Unit Price	Extended Price	Low Unit Price	High Unit Price	Median Unit Price	Average Unit Price	
731	207	STOCKPILE AND RESET TOP 12 INCHES OF TOPSOIL OR IMPORT NEW FROM SOURCE APPROVED BY ENGINEER. KEEP FREE FROM DEBRIS. PLACE AT 90% MAX DENSITY WITH TOP 3" LOOSENEED FOR SEED BED.	1,000.	SY	\$ 4.00	\$ 4,000.00	\$ 2.50	\$ 2,500.00	\$ 8.80	\$ 8,800.00	\$ 4.70	\$ 4,700.00	\$ 4.00	\$ 4,000.00	\$ 2.50	\$ 8.80	\$ 1,250.00	\$ 5.00	
900	209/108.12	DUST ABATEMENT	60.	DAYS	\$ 85.00	\$ 5,100.00	\$ 70.00	\$ 4,200.00	\$ 57.00	\$ 3,420.00	\$ 30.00	\$ 1,800.00	\$ 700.00	\$ 42,000.00	\$ 30.00	\$ 700.00	\$ 900.00	\$ 214.25	
901	620	PORTABLE SANITARY FACILITIES (MULTIPLE LOCATIONS NOT PAID SEPARATELY	60.	DAYS	\$ 11.00	\$ 660.00	\$ 5.00	\$ 300.00	\$ 11.00	\$ 660.00	\$ 11.00	\$ 660.00	\$ 20.00	\$ 1,200.00	\$ 5.00	\$ 20.00	\$ 150.00	\$ 11.75	
902	625	CONSTRUCTION SURVEYING, INCLUDING AS-BUILT DRAWINGS	1.	LS	\$ 20,000.00	\$ 20,000.00	\$ 12,000.00	\$ 12,000.00	\$ 12,113.00	\$ 12,113.00	\$ 10,000.00	\$ 10,000.00	\$ 13,500.00	\$ 13,500.00	\$ 10,000.00	\$ 13,500.00	\$ 5,000.00	\$ 11,903.25	
902A	629	REFERENCE AND RESET SURVEY MONUMENT (PROPERTY PINS TO BE REFERENCED AND RESET AS INCIDENTAL ITEM).	5.	EA	\$ 800.00	\$ 4,000.00	\$ 250.00	\$ 1,250.00	\$ 216.00	\$ 1,080.00	\$ 350.00	\$ 1,750.00	\$ 360.00	\$ 1,800.00	\$ 216.00	\$ 360.00	\$ 540.00	\$ 294.00	
903	626	MOBILIZATION	1.	LS	\$ 45,000.00	\$ 45,000.00	\$ 58,000.00	\$ 58,000.00	\$ 83,288.00	\$ 83,288.00	\$ 54,500.00	\$ 54,500.00	\$ 108,000.00	\$ 108,000.00	\$ 54,500.00	\$ 108,000.00	\$ 27,250.00	\$ 75,947.00	
904	630	TRAFFIC CONTROL PLAN	1.	LS	\$ 1,300.00	\$ 1,300.00	\$ 825.00	\$ 825.00	\$ 165.00	\$ 165.00	\$ 300.00	\$ 300.00	\$ 900.00	\$ 900.00	\$ 165.00	\$ 900.00	\$ 82.50	\$ 547.50	
905	630	TRAFFIC CONTROL (COMPLETE IN PLACE)	1.	LS	\$ 12,000.00	\$ 12,000.00	\$ 5,000.00	\$ 5,000.00	\$ 8,306.00	\$ 8,306.00	\$ 13,100.00	\$ 13,100.00	\$ 12,000.00	\$ 12,000.00	\$ 5,000.00	\$ 13,100.00	\$ 2,500.00	\$ 9,601.50	
906	630	TRAFFIC CONTROL FLAGGING HOURS	220.	HRS	\$ 24.00	\$ 5,280.00	\$ 22.00	\$ 4,840.00	\$ 20.55	\$ 4,521.00	\$ 21.00	\$ 4,620.00	\$ 25.00	\$ 5,500.00	\$ 20.55	\$ 25.00	\$ 2,260.50	\$ 22.14	
907	208	STORMWATER MANAGEMENT PLAN IMPLEMENTATION	1.	LS	\$ 11,000.00	\$ 11,000.00	\$ 1,500.00	\$ 1,500.00	\$ 3,250.00	\$ 3,250.00	\$ 3,000.00	\$ 3,000.00	\$ 1,500.00	\$ 1,500.00	\$ 1,500.00	\$ 3,250.00	\$ 750.00	\$ 2,312.50	
908	GCC56	WEEKLY NEWSLETTERS (APPROXIMATELY 400 PER DISTRIBUTION)	1.	LS	\$ 7,000.00	\$ 7,000.00	\$ 2,600.00	\$ 2,600.00	\$ 2,150.00	\$ 2,150.00	\$ 3,000.00	\$ 3,000.00	\$ 4,000.00	\$ 4,000.00	\$ 2,150.00	\$ 4,000.00	\$ 1,075.00	\$ 2,937.50	
		0																	
MCR		Minor Contract Revisions	---	---	\$ 80,000.00	\$ 80,000.00	\$ 80,000.00	\$ 80,000.00	\$ 80,000.00	\$ 80,000.00	\$ 80,000.00	\$ 80,000.00	\$ 80,000.00	\$ 80,000.00	80,000.00	80,000.00	80,000.00	80,000.00	
		TOTAL BID:				\$ 1,691,379.00		\$ 1,299,027.00		\$ 1,338,639.60		\$ 1,471,998.38		\$ 1,833,905.00					
		[1] - corrected extension																	
		[2] - corrected total																	